

APPENDIX “A-1”

LOCATIONS OF WORK

Project # STL403

Q:\Engineering\All Projects\STL\STL403 Cross Gtr Rehab FY14-15\Specs\STL403 Contract.doc

APPENDIX "A-1"

CROSS GUTTER REHABILITATION CITYWIDE FY2014-2015 STL403

Location #	LOCATION	GRINDING (SF)	6" CAB (SF)	CROSS GTR PER CVCS-2 (SF)	CURB & GTR (LF)	SIDEWALK (SF)	ALLEY, DWY (SF)	ADA PED RAMPS PER CVCS 25 (EA)	ADA PED RAMPS PER CVCS 27 (EA)	ADA PED RAMPS PER CVCS28 (EA)	REMOVAL PAVEMENT MARKING (LF)	STRIPE IN PAINT WITH PM (LF)	STRIPING IN THERMOPLASTIC (SF)	LADDER CROSSWALK THERMOPLASTIC (SF)	STRIPING LEGEND (EA)	PAINT RED CURB (LF)	RELOCATE SIGN (EA)	INSTALL SIGN (EA)	ADJUST MANHOLE (EA)	PL Markers (City Staff)
10	"K" ST & DEL MAR AVE	1120	555	550				2					17			30				
11	"K" ST & CHURCH AVE	1050	540	550				2					17		1	30	1			
12	109 MANKATO ST	560	275	230								30								
13	111 WHITNEY ST	570	275	230	38							30								
14	FIRST AVE & SHASTA ST	1110	545	650				2					18			30				
15	MONSERATE AVE & E PROSPECT ST	840	420	350	24			2				40	18							
16	MONSERATE AVE & E NAPLES ST	1750	670	940	15			2				20	40	990	1					
	MISCELLANEOUS					20	100		1	1	30							1		
	CONTRACT TOTALS	7000	3280	3500	77	20	100	10	1	1	30	120	110	990	2	90	1	1	0	0
	6" CAB (TONS), 130 PCF		106.6	113.75																
	4" AC (TONS), 148 PCF		80.91	86.3333																
	1.5" AC (TONS), 148 PCF	64.75																		

APPENDIX “A-2”

SUPPLEMENTAL LIST OF LOCATIONS

Project # STL403

Q:\Engineering\All Projects\STL\STL403 Cross Gtr Rehab FY14-15\Specs\STL403 Contract.doc

APPENDIX "A-2"

SUPPLEMENTAL LOCATIONS
CROSS GUTTER REHABILITATION CITYWIDE FY2014-2015 STL403

Location #	LOCATION	GRINDING (SF)	6" CAB (SF)	CROSS GTR PER CVCS-2 (SF)	CURB & GTR (LF)	SIDEWALK (SF)	ALLEY, DWY (SF)	ADA PED RAMPS PER CVCS 25 (EA)	ADA PED RAMPS PER CVCS 27 (EA)	ADA PED RAMPS PER CVCS28 (EA)	REMOVAL PAVEMENT MARKING (LF)	STRIPE IN PAINT WITH PM (LF)	STRIPING IN THERMOPLASTIC (SF)	LADDER CROSSWALK THERMOPLASTIC (SF)	STRIPING LEGEND (EA)	PAINT RED CURB (LF)	RELOCATE SIGN (EA)	INSTALL SIGN (EA)	ADJUST MANHOLE (EA)	PL Markers (City Staff)
17	SMITH AVE 428-434	950	468	240	18	15	138			2										
18	FIRST AVE & I ST (Future Install)																			
19	COLORADO AVE & HALSEY ST	932	474	470				3					20		1			1		
20	CORTE MARIA AVE & MURRAY ST	1772	685	933					2				36	851	1	120				
21	CUYAMACA AVE & E DONAHOE ST	1337	507	592				1	1				20		1					
22	WOODLAWN AVE & I ST	1312	600	689				2					34	732						
23	FIRST AVE & KING ST	1093	540	566									17		1					
	CONTRACT TOTALS	7396	3274	3490	18	15	138	6	3	2	0	0	127	1583	4	120	0	1	0	0
	6" CAB (TONS), 130 PCF		106.41	113.43																
	4" AC (TONS), 148 PCF		80.76	86.09																
	1.5" AC (TONS), 148 PCF	68.41																		